This drawing is the copyright of High Lane Design. Reproduction, publication or any other usage of this drawing without permission of the company is against the the law.

Do not scale. The contractor shall verify all dimensions and existing conditions on site prior to commencing the works.

This drawing should be read in conjunction with all other relevant documents.

Revisions :	Date :	By :
Revision A - Planning Issue	09.12.21	SP
Revision B - OPTIONS FOR DIVERSION ADDED	11.02.22	SP

Proposed Footpath and Bridleway Works

1. Temporary closure of footpath 18 between points A and B to allow for work to be carried out to upgrade to a Bridleway.
2. Construction of new Bridleway between points B and C to allow development to proceed in accordance with planning approval.
3. Permanent closure of Bridleway between points A and C being replaced with new Bridleway between points A to B to C.
4. Construction of new footpath between points D and F.
5. Closure of unadopted Footpath between points D and E.
6. Construction of new unadopted Bridleway between points G and H.

Footpaths to be 2.0m wide throughout
Adopted footpaths to be finished in MOT Type 1 material.

Unadopted footpaths to be earth finish to match existing

Bridleways to be 3.0m wide where unfenced increasing to 4m wide where fenced on both side.
Adopted Bridleways to be finished in MOT type 1 material and laid with camber to provide drainage

All signage will be provided in accordance with 'Waymaking Public Rights of Way' produced by Natural England

- Existing Bridle Path
- Existing Footpath
- Existing Unadopted Footpath
- Existing Unadopted Footpath to be Diverted
- Existing Bridle Path to be Diverted
- Proposed New Route of Unadopted Footpath
- Route of Diverted Bridle Path
- Proposed New Unadopted Bridle Path
- Existing Footpath Upgraded to Bridle Path

high lane design

199 High Lane West
West Hallam
Ilkeston
Derby
DE7 6HP

m: 07816 513918
t : 0115 944 3251
e : highlanedesign@hotmail.com

Project

Proposed Development - Denby

Drawing

Site Plan as Proposed
Proposed Works to Footpaths and Bridleways

Scale :	Date :	Drawn by :	Checked by :
1:2000@A1	Dec.'21	SP	

Job number :	Drawing number :	Revision:
L265	SP112	C