Planting Schedule

INDIVIDUAL TREES

Qty	Latin Name	Common Name	Height	Form	Root Condition	Minimum Clear Stem	Girth
4	Amelanchier x grandiflora 'Robin Hill'	Apple Serviceberry	350-400cm	Heavy Standard	RB	Min 175cm	12-14cm
16	Magnolia x loebneri 'Merrill'	Magnolia 'Merrill'	350-425cm	Standard	RB/L	Min. 175cm	12-14cm
9	Prunus 'Snow Goose'	Flowering Cherry 'Snow Goose'	350-425cm	Heavy Standard	RB	Min. 200cm	12-14cm
3	Prunus 'Spire'	Flowering Cherry 'Spire'	300-350cm	Standard	RB	Min. 175cm	10-12cm
1	Sorbus 'Joseph Rock'	Rowan 'Joseph Rock'	300-350cm	Standard	RB	Min. 175cm	10-12cm
1	Sorbus 'Sunshine'	Rowan 'Sunshine'	300-350cm	Standard	RB	Min. 175cm	10-12cm
7	Sorbus vilmorinii	Vilmorin's Rowan	300-350cm	Standard	RB	Min. 175cm	10-12cm

HEDGEROWS (planted in a single row, 5 plants lin/m)

Qty	Latin Name	Common Name	Height	Form	Root Condition
349	Choisya ternata	Mexican Orange	40-60cm	5-7.5L	C
573	Photinia x fraseri 'Little Red Robin'	Little Red Robin Photinia	40-60cm	5-7.5L	C
877	Pittosporum tenuifolium	Kohuhu	30-40cm	5L	C
318	Spiraea japonica	Japanese Spiraea	40-60cm	5-7.5L	C

PLANTING BEDS

Qty	Latin Name	Common Name	Height	Container Size	Rate/Plants m²
67	Brachyglottis 'Sunshine'	Shrub Ragwort 'Sunshine'	40-60cm	5-7.5L	3
27	Ceanothus thyrsiflorus repens	Creeping Blueblossom	40-60cm	5L	3
47	Ceratostigma willmottianum	Chinese Plumbago	30-40cm	5L	3
115	Choisya ternata	Mexican Orange	40-60cm	5-7.5L	3
14	Choisya ternata 'Sundance'	Sundance Mexican Orange Blossom	40-60cm	5L	3
116	Cistus x corbariensis	Hybrid Rock Rose	40-60cm	5-7.5L	3
69	Escallonia 'Apple Blossom'	Escallonia 'Apple Blossom'	40-60cm	5L	3
14	Escallonia laevis 'Gold Ellen'	Escallonia 'Gold Ellen'	40-60cm	5L	3
81	Euonymus japonicus 'Aureus'	Golden Japanese Spindle	30-40cm	5L	3
70	Euonymus japonicus 'Bravo'	Japanese Spindle 'Bravo'	40-60cm	5L	3
77	Fatsia japonica 'Variegata'	Variegated Japanese Aralia	30-40cm	3L	3
29	Hypericum x 'Hidcote'	Hidcote St. John's Wort	30-40cm	5L	3
72	Ilex crenata 'Convexa'	Convexa Japanese Holly	30-40cm	5L	3
29	Lavandula angustifolia 'Hidcote'	Lavender 'Hidcote''	20-30cm	5L	3
181	Lonicera nitida 'Maigrun'	Box Honeysuckle 'Maigrün'	30-40cm	5L	3
67	Photinia x fraseri 'Pink Marble'	Christmas Berry 'Pink Marble'	40-60cm	5-7.5L	3
77	Pittosporum tenuifolium 'Tom Thumb'	Kohuhu 'Tom Thumb'	20-30cm	5L	3
27	Pittosporum tobira 'Nanum'	Dwarf Japanese Mock Orange	30-40cm	5-7.5L	3
67	Potentilla fruticosa 'Goldfinger'	Goldfinger Potentilla	30-40cm	5-7.5L	3
27	Rosmarinus officinalis	Rosemary	40-60cm	5L	3
29	Rosmarinus officinalis 'Miss Jessopp's Upright'	Rosemary 'Miss Jessopp's Upright'	30-40cm	5L	3
67	Sarcococca confusa	Sweet Box	30-40cm	5L	3
245	Sarcococca hookeriana var. digyna	Christmas Box / Sweet Box	30-40cm	5L	3
66	Skimmia japonica 'Veitchii'	Japanese Skimmia 'Veitchii'	30-40cm	5L	3
115	Skimmia x confusa 'Kew Green'	Skimmia 'Kew Green'	30-40cm	5L	3
102	Spiraea japonica	Japanese Spiraea	40-60cm	5-7.5L	3
47	Spiraea japonica 'Little Princess'	Japanese Spirea 'Little Princess'	30-40cm	5L	3
102	Viburnum davidii	David Viburnum	30-40cm	5-7.5L	3
2062					

SPECIMEN SHRUBS

Qty	Latin Name	Common Name	Height	Container Size	Root Condition
2	Cornus mas	Cornelian Cherry	80-100cm	10L	C



NOTES

This drawing is the property of FPCR Environment and Design Ltd and is issued on the condition it is not reproduced, retained or disclosed to any unauthorised person, either wholly or in part without written consent of FPCR Environment and Design Ltd.

0 25 50 75 100m

N

KEY

- Site Boundary
- Proposed Trees
- Proposed Specimen Shrubs
- Proposed Single-species Hedgerow
- Proposed Planting Beds
- Proposed Turf/Amenity Grass

NOTES:
1. For detailed POS proposals, please refer to drawings 11339-FPCR-XX-XX-DR-L-xxxx.
2. All proposed trees to be double staked and secured with adjustable ties.
3. Planting mixes to be planted in groups of 3-5 plants per species, with the taller plants places to the rear of the border.
4. Planting within visibility splays to be kept below 600mm in height.
5. All trees were selected to avoid any influence on dwelling foundations.

rev	date	description	drn	chk
P05	07/03/2023	Additional trees along avenue and updated proposals at plot 117/118	IAM	/ IAM
P04	27/02/2023	Amendments post comments Added landscape parking brakes	SJL	IAM
P03	24/02/2023	Amended to new layout	SJL	OFD
P02	13/12/2022	Updated to new layout.	PJM	OFD
P01	02.12.2022	First issue	IAM	DH

masterplanning
environmental assessment
landscape design
urban design
ecology
architecture
arboriculture

FPCR Environment and Design Ltd
Lockington Hall
Lockington
Derby
DE74 2RH

t: 01509 672772
e: mail@fpcr.co.uk
w: www.fpcr.co.uk

client
Miller Homes

project
Land off Stanley Street, Somercotes

drawing title
Detailed On-plot Planting Plan
General Assembly

scale	drn	chk	date created
1:1000 @ A1	IAM	DH	02 DECEMBER 2022

project number	status	issue
11339	S03	P05

document number
11339-FPCR-XX-XX-DR-L-0001
Project Code - Originator - Zone - Level - Type - Role - Drawing Number

File: L:\11300\11339\LANDS\Drawings\11339 - On-plot Planting (P04).vwx