

71.600 m 03 - Second Floor
68.100 m 02 - First Floor
64.500 m 01 - Ground Floor
61.500 m 00 - Plant Level
60.375 m 00 - Lower Ground Floor Level

North Elevation
1 : 100



71.600 m 03 - Second Floo
68.100 m 02 - First Floor
64.500 m 01 - Ground Floo

East Elevation (Derby Road)
1 : 100



Graphical Scale 1:100 0 1 2 3 4 5m

Drawn by : AJP Date : 23/07/2021 Scale : As indicated @ A1

Status	Preliminary	Presentation	Tender	Construction	Last Issue
Date :	23/07/21				
Approved by :	PF				

Revision		Date	Drawn	Approved
P01	First Issue	23/07/21	AJP	PF
P02	Revised following reposition of building and changes to extent of lower ground floor area	16/09/21	AJP	PF
P03	Material notes added, PV panels indicated and dormer roofs updated	13/01/22	MDC	PF
P04	Draft issue for Planning	13/05/22	MDC	PF
P05	Issued for Planning	16/06/22	MDC	PF
P06	Sunken courtyard omitted	29/07/22	MDC	PF
P07	Updated following Client changes.	16/11/22	PDS	PF
P08	Conservation Officer's comments addressed.	08/03/23	PDS	PF
P09	Updated in line with design developement	10/03/23	JW	DK
P10	Inverted dormers proposed, following Conservation Officer's comments.	08/08/23	PDS	PF

LEGEND

01	Clay Facing Brickwork
02	Recessed Facing Brickwork Panels with Alternate Recessed Brick Course Banding
03	Recessed Clay Facing Brickwork
04	Ashlar Smooth-faced Stone Wall
05	Natural Slate NB - Reclaimed slate to Link roof
06	Single ply roofing
~~07~~	~~Zinc/Metal Standing Seam~~
08	PPC Aluminium Window System NB - Clear glass, unless marked otherwise
09	PPC Aluminium Curtain Wall System
10	PPC Aluminium Doorset Glazed/Solid Panels
11	PPC Steel Doorset
~~12~~	~~PPC Aluminium Spandrel Panel (Colour TBC)~~
13	PPC Steel Louvred Doorset
14	Recessed Ashlar Smooth-faced Stone Wall
15	Opaque glazed 'Look a Like' Panels
16	Fritted glass / privacy film to glass (Locations TBC)
17	Louvred Screens / Gates
18	PPC Vertical railing balustrade with handrail
19	Roof Access Walkway - PPC Metal (Colour TBC)
20	Bespoke Vertical Bar Gates
21	Integrated Photovoltaic Panels - flush with roof finish
22	PPC Metal Louvre Panel
23	Projecting Window
24	Reclaimed Textured-faced Stone Wall
25	PPC Aluminium Gutter and Rainwater Pipes
26	Faunal Species Boxes NB - Refer to Ecologist report for details
27	Substation
28	Permeable Hardstanding/Paving

Race Cottam Associates
Sheffield Studio
1 East Parade
Sheffield S1 2ET
0114 273 7050
Architects
racecottam.com

Client: DCHS Trust

Project : Belper Health Centre

RCA Project Ref: 3160-13

Drawing Title : Proposed_GA_Elevations_Sheet_1

Drawing Number:

A5057	RCA	00	XX	DR	A	0254
Project Code	Originator	Volume	Level	File Type	Role	Number

Status:	Suitability Description:	Revision Description:	Revision:
S4	Stage Approval	PRELIMINARY	P10

© This drawing is the copyright of Race Cottam Associates Ltd. Do not scale from this drawing.