Work Schedule

Client Name:	Shine at the Hollies	**Contact Numbers:**	Telephone: Mobile: [redacted]
Site Contact Name:	Lisa Langhorn	**Site Specific Ref No:**	
Contact No:		**Business Name:**	Shine at the Hollies
Site Address:	The Hollies 105 Bridge street Belper Derbyshire DE56 1BA		

Work Items

Quote Number: 5921

No: T1

Type: Common Beech

Details: Full crown reduction by up to 2-3m. Tipping back to draw the crown away from buildings and roofs. Use MEWP to access the tree, access for MEWP requires part of the railings to be unbolted and a couple of Laurel to be dug out and put back in after work completion. Justification - this tree has been reduced to the same completed size in the past,a re-reduction to previous points will maintain a large tree growing close to property and garden targets.







No: T2

Type: Common Horse chestnut

Details: Crown Lift to provide 5.2 metres clearance from ground level road side and 4m over property side. Tip back from neighbouring property for 2m clearance. Remove all arisings.



