





Graphical Scale 1:100 (0 1 2 3 4 5m)

Drawn by : AJP Date : 23/07/2021 Scale : As indicated @ A1

Status	Preliminary	Presentation	Tender	Construction	Last Issue
Date :	23/07/21		04/10/23	27/02/25	10/06/26
Approved by :	PF		PDS	PDS	PDS

Revision		Date	Drawn	Approved
C01	Stage 4. Issued for Stage Approval.	27/02/25	PDS	PDS
C02	Drawing updated in-line with current proposlas. (S4) Issue.	02/12/25	PDS	PDS
C03	Construction Record Issue.	22/07/26	PDS	PF

RACE COTTAM ASSOCIATES LIMITED

This drawing generally reflects the final issued construction status drawing.
All known minor amendments made during the build process have been incorporated, but it cannot be guaranteed that all amendments have been included or that the building has been constructed to the exact size, configuration and detail represented on this drawing.
New surveys should be undertaken where necessary for any future works.
Where our design intent has been developed by the relevant specialist subcontractors, the drawings, details and specifications provided by the relevant subcontractor(s) take precedence and should be referred to.

Compliance with ADB is achieved by means of Material Specification;
Roof sheets (Kingspan RW1000) - BRoof (T4)
Metsec Purlins - Class A1,
Datasheets Provided by Main Contractor.

LEGEND

01	Clay Facing Brickwork
02	Recessed Facing Brickwork Panels with Alternate Recessed Brick Course Banding
03	Recessed Clay Facing Brickwork
04	Ashlar Smooth-faced Stone Wall
05	New Natural Slate Roof
06	Single ply roofing
07	Secret fix Aluminium capping to top of gable ends and parapets
08	PPC Aluminium Window System NB - Clear glass, unless marked otherwise
09	PPC Aluminium Curtain Wall System
10	PPC Aluminium Doorset Glazed/Solid Panels
11	PPC Steel Doorset
12	Door Barrier protection guard-hoops, PPC Steel
13	PPC Steel Louvred Doorset
14	Recessed Ashlar Smooth-faced Stone Wall
15	Opaque glazed 'Look a Like' Panels
16	Fritted glass / privacy film to glass (Locations TBC)
17	Louvred Screens / Gates
18	PPC Vertical railing balustrade with handrail
19	Roof Access Walkway - PPC Metal (Colour TBC)
20	Bespoke Vertical Bar Gates
21	Integrated Photovoltaic Panels - flush with roof finish
22	PPC Metal Louvre Panel
23	Projecting Window
24	Reclaimed Textured-faced Stone Wall
25	PPC Aluminium Gutter and Rainwater Pipes
26	Faunal Species Boxes NB - Refer to Ecologist report for details
27	Substation
28	Permeable Hardstanding/Paving
29	Recessed Facing Brickwork Panel

RCA.
Race Cottam Associates.
Sheffield Studio | 1 East Parade | Sheffield | S1 2ET
0114 273 7050
Architects racecottam.com

Client:
Henry Brothers

Project :
Belper Integrated Health Hub

RCA Project Ref:
3542-02

Drawing Title :
Proposed GA Elevations Sheet 2

Drawing Number:

Project Code	Originator	Volume	Level	File Type	Role	Number
A5057	RCA	V1	ZZ	DR	A	0255

Status:	Suitability Description:	Revision Description:	Revision:
CR	Construction Record	LAST ISSUE	C03

© This drawing is the copyright of Race Cottam Associates Ltd. Do not scale from this drawing.