0 1 2 3 4 5

PROJECT MANOR FARM, DETHICK

DRAWING PROPOSED FF CHANGES TO AREAS 24 + 26

SCALE 1:50 @ A3

DATE AUG 2022

DRAWING NO 11602/101A

MARTIN TUCKER LTD
Architectural Services & Interior Designers

Low Leas Barns
Low Leas
Riber
Derbyshire
DE4 5JR

T. 01629 530707
M. 07771 565439
W. martin tucker.net
E. m.tucker55.mt@gmail.com

The title, copyright and confidential information in this document belongs to Martin Tucker Ltd. All rights reserved. You may not reproduce this document or disclose it to others without the written consent of Martin Tucker Ltd, who also accepts no liability for the misuse by others in whole or in part. **Do not scale.**

NIB RETAINED + BOTTOM OF TRUSS RAISED ALSO RETAINED

MODERN STUD REMOVED + DOOR F13 WALL BEHIND MADE GOOD WITH LIME PLASTER TO MATCH

DOOR F12 RETAINED
DOOR F15 REMOVED

NEW STUD WALL FORMED WITH PB + LIME SKIM BOTH SIDES SOUNDPROOFING REQUIRED BY CLIENT

BEAM OVER EXPOSED IN APPLICATION + SEE OTHER PHOTOS

Landing
Ceiling Ht: 2.41
FL: 193.51m

Landing
Ceiling Ht: 2.37
FL: 194.34m

Bedroom
Ceiling Ht: 2.70
FL: 194.23m

BATHROOM 26

Master Bedroom 29
Ceiling Ht: 2.21
FL: 194.34m

Bathroom
Ceiling Ht: 2.40
FL: 194.31m

Ceiling Ht: 2.73
FL: 194.32m

Section A.

Section B.